

Combined Ex-situ and In-Situ Remediation of Soil and Groundwater Impacts to Meet Site Closure Requirements

*Presented by:
Robert Tossell*

April 2010



© Pinchin Environmental Ltd. - All Rights Reserved



Engineering Environmental and
Health & Safety Solutions

Agenda and Acknowledgements

- Comparison and contrast of two Sites
 - Site background and objectives
 - Site management approaches
 - Implementation/results
 - Status of each Site
-
- Yu Li – Pinchin
 - Paul Zizec - Hazco

Site Management Objectives

- Site 1
 - remediation for financing
 - clean up to Ontario Ministry of Environment (MOE) commercial /industrial standards in two years
- Site 2
 - property sale
 - had to meet MOE commercial /industrial standards in a 5 to10 years

Background on Sites

Site 1

- Commercial/light industrial
- Solvent and waste oil recycling depot
- Hydrocarbons and chlorinated solvents (TCE) found in subsurface located near a floor drain

Site 2

- Commercial/light industrial
- Automotive repair for 23 years
- Hydrocarbons and chlorinated solvents (1,1,1-TCA, TCE) used and disposed of in below slab hoist pit
- Hoist pit comprised of concrete and steel

Site Conditions

	Site 1	Site 2
Soil Types	Fill and silty/clay over clay	Sand over silty clay
Depth to groundwater (meters below grade)	2.3 (0.5)	2.5 (1.3)
Depth to confining layer (meters below grade)	3.5	6.5
Estimated hydraulic conductivity (cm/sec)	10^{-4} to 10^{-5}	10^{-3}

Site 1

Site 1: Options for Management?


- Feasibility study evaluated several technologies:
 - Monitored natural attenuation (too long, likely to take more than 2 years);
 - In-situ chemical oxidation (“ISCO”) for soil and groundwater (costs were high due to oxidant demands, timeframe unknown);
 - Soil excavation and in-situ bioremediation of groundwater (in situ bioremediation produces biogases);
 - Soil excavation and ISCO for groundwater (selected option)

Design – Site 1

Site 1:

- Excavation with infiltration gallery/recirculation system to treat groundwater
- system design for both in situ bioremediation or ISCO
- ISCO was selected over bioremediation due to concerns with biogas production and timeline


Implementation – Site 1



Implementation - Site 1

- Injection wells installed early December 2008
- Soil excavation late December 2008
- Infiltration gallery built in January 2009
- Permanganate injection in March 2009
- Performance monitoring April, May, July and December 2009

Infiltration gallery

















Site 1: Results

- Excavation of 65 tonnes of hydrocarbon impacted soil
- Soil sampling of indicated that excavation sidewall and base met MOE standards
- Recirculation system was successful for mixing permanganate and treating groundwater
- Concentrations of CVOCs decreased rapidly following ISCO injection and recirculation

MW 101



MW 102



Site 2

Site 2: Options for Management?

- Feasibility study evaluated several technologies (greater flexibility due to timeframe)
 - Excavation of soil near point of release (limited effect)
 - Excavation/recovery (only option considered due to free phase hydrocarbons/VOC mixture)
 - Monitored natural attenuation (for distal portion of plume)
 - Air Sparging/Biosparging;
 - ISCO for residual soil impacts and groundwater

Design – Site 2

Site 2:

- Excavation with delivery/recovery for LNAPL
- System design for both in situ bioremediation or ISCO
- Unique substrate delivery system installed using horizontal drilling
- MNA for solvent plume


Implementation – Site 2

LEGEND

- MNA SAMPLING LOCATION
- MONITORING WELL ADVANCED BY PINCHIN MAY 2009
- BOREHOLE ADVANCED BY PINCHIN MARCH/APRIL 2007
- MONITORING WELL ADVANCED BY PINCHIN FEBRUARY/MARCH 2007
- MONITORING WELL DECOMMISSIONED DURING INFILTRATION GALLERY INSTALLATION
- INFILTRATION GALLERY


APPROXIMATE SITE BOUNDARY

EXTENT OF EXCAVATION



LEGEND

- MNA SAMPLING LOCATION
- MONITORING WELL ADVANCED BY PINCHIN MAY 2009
- BOREHOLE ADVANCED BY PINCHIN MARCH/APRIL 2007
- MONITORING WELL ADVANCED BY PINCHIN FEBRUARY/MARCH 2007
- MONITORING WELL DECOMMISSIONED DURING INFILTRATION GALLERY INSTALLATION
- INFILTRATION GALLERY



Implementation - Site 2

- Soil excavation late March 2009
- Permanganate injection in bottom of excavation to treat residual chlorinated solvents (2009)
- Installation of horizontal substrate delivery system April 2009
- Product recovery system installation date (fall 2009)
- MNA monitoring began in May 2009









Status of Each Site

Site 1

- No residual soil impacts
- Groundwater recirculation system shut-down in late 2009
- Only one groundwater sample vinyl chloride concentration exceeds MOE criteria
- Sampling to evaluate confirm groundwater results
- File for an RSC

Site 2

- 250 tonnes of soil removed
- Recovery system to be installed in late 2010/early 2011
- MNA to evaluate residual hydrocarbons and chlorinated solvents
- In situ bioremediation or possibly ISCO to treat residual hydrocarbon in source area during or following free phase recovery

Questions?

For more information:
rtossell@pinchin.com
or visit pinchin.com

